



TOSHIBA



Integration and Test of the ATLAS Central Solenoid

Roger Ruber


for the ATLAS CS team,

LAr Meeting, CERN, 26-27 January 2004

Contents

1. Introduction
2. Progress Report
3. On-surface Integration
4. On-surface Test
5. Conclusions

Introduction



Solenoid Layout

Thin superconducting
central solenoid:

$$B_c = 2T \quad (I = 7600A)$$


$$5.3m \times \phi 2.3m \times 45mm$$

$$\text{wall thickness} = 0.66 X_0$$



$$E/M = 7.1 \text{ kJ/kg}$$

System consists of:

- A. thin solenoid coil
- B. chimney
- C. control dewar +
proximity cryogenics



Factory Test in Japan



Progress Report

2001:

- delivery components

2002-2003:

- proximity cryogenics
- chimney
- power supply
- cryogenics control
- survey

In progress:





- magnet control system
- magnet safety system
- solenoid integration



Chimney Test Results

- excitation up to 9 kA
- verified safety of the design:
 - mass flow stop to SQD trip:
28min. until quench
- proximity cryogenics and control
 - dynamic heat balance:
heater up to 70W(cooling line) +3W(LHe level)
 - 150m capillary for (differential) pressure transducers

Survey October 2003




potentiometer

Survey Results



- coil with respect to IWV
 - vertical offset -1.6 to -2.6 mm
 - axial centre of the winding
 - warm: at -13.1mm
 - cold: at -0.1mm (4K, 2T)
 - error bars in order of 0.3 to 0.5 mm
- observed permanent axial shrinkage is
 - 1.6mm (potentiometer) - 1.8mm (optical survey)
- circularity solenoid end flanges
 - end A: +/- 2.7mm ; end C: +/-1.3mm

On-surface Integration




Mechanical Integration

January 2004







Services Integration




Conductor: 4 cables, main + side, supply & return
Cryogenics: 4 tubes, 4.5K + 80K, supply & return

Integration Work



On-surface Test



Test Objectives

- confirm operation
 - run at nominal current + 5% (8kA)
 - safety for quench
- study interaction with detector
 - influence of magnetic field and eddy currents
 - thermal shielding of warm coil & bulkhead
- test final control and safety systems
 - including interlock with detector

Test Schedule

	Week																			
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
	cool down					filling		test			warm up									
detector	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
							test		warm up											
magnet					█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█

- cool down magnet (1 – 2 weeks)
 - in parallel with detector
- magnet test (2 weeks)
 - confirm operation in parallel with LAr filling
 - interaction studies in begin phase detector test
- warm up of magnet
 - monitor temperature distribution with cold detector

Conclusions

- all components manufactured & tested
- successful commissioned chimney and proximity cryogenics
- confirmed safe chimney operation at 9kA and in event of cryogenics' failure
- survey of CS+IWV completed
- ready for full on-surface test by March


Acknowledgements

All my colleagues at

- **KEK:**
for design and test
- **CERN and ATLAS:**
for integration and on-surface test
- **Toshiba Co.:**
for realization of the solenoid and welding machine

Back-up Slides

Factory Test Results



- maximum current 8.4kA (chimney: 10kA)
- quench & cooling flow stop tests up to 7.6kA

Bulkhead Mock-up




Services Integration UX15

Field work:


3 permanent joints

- 4 cooling tubes: 4.5K + 80K, supply & return (qualification ISO10042-B).
- 4 SC cables: main + side, supply & return

An orbital welding machine has been developed by Toshiba.



Welding Scheme



central insert, adjustable in length, edge of 30°

- pipe $\phi 18\text{mm}$ ($t=2\text{mm}$); insert $\phi 21$ ($t=3.5\text{mm}$)
- pipe $\phi 24\text{mm}$ ($t=3\text{mm}$); insert $\phi 27$ ($t=4.5\text{mm}$)

pipe is A6063; insert is A5083